

INDEX

Sl. No.	Description	Page No.
1	Earth Work Excavation and Rubble Foundation	
2	Filling Basement	
3	Block Work	
4	RCC Lintel	
5	RCC Sunshade, RCC Stair, RCC Slab, Parapet Work	
6	PCC	
7	Reinforced Steel	
8	Cement	
9	Sand	
10	Ceiling Plastering	
11	Inside Plastering	
12	Outside Plastering	
13	Terrace Plastering	
14	Septic Tank and Rainwater Tank	
15	Electrical Work	
16	Details of Electrical Points	
17	Plumbing and Sanitary Work	
18	Sanitary Price Details	
19	Details of Plumbing Points	
20	Hand Rails	
21	Flooring Tiles	
22	Skirting Tiles	
23	Kitchen Dadoing	
24	Kitchen Top	
25	Bathroom Flooring	
26	Bathroom Wall Tile	
27	Bathroom Doors	
28	Putty and Paint	
29	Joinery Details	
30	Conclusion of Work	
31	Payment Schedule	
32	Inclusion and Exclusion	
33	Terms and Conditions	

SCOPE OF WORK

EARTH WORK EXCAVATION AND RUBBLE FOUNDATION:

Foundation trenches, Rubble work etc.

Excavation	60 x 60cm in size
Rubble foundation	60 x 60 cm in size
Rubble basement	45 x 30 cm in size
Belt	30 x 15 cm in size

FILLING BASEMENT:

Filling in basement shall be done with red earth (Depends on availability). All filling soil shall be watered and well compacted.

SOLID BLOCK WORK / LATRATE STONE WORK:

Good quality Solid Block in 20 cm thick; cement mortar in 1:6 ratio or using good quality of Chenkallu (Depends on availability)

RCC LINTEL:

Providing & laying controlled reinforced cement concrete as per standard structural and architectural specification using 20MM downsized aggregates at any depth or heights including all formworks, centering, shuttering, scaffolding, compacting with vibrators, and curing.

Concrete mix shall be of (1:2:4) grade.

RCC SUNSHADES: (Above windows only):

Providing & laying controlled reinforced cement concrete as per standard structural and architectural specification using 20MM downsized aggregates at any depth or heights including all formworks, centering, shuttering, scaffolding, compacting with vibrators and curing.

Concrete mix shall be of (1:2:4) grade.

RCC STAIRS:

Providing & laying controlled reinforced cement concrete as per standard structural and architectural specification using 20MM downsized aggregates at any depth or heights including all formworks, centering, shuttering, scaffolding, compacting with vibrators and curing.

Concrete mix shall be of (1:2:4) grade.

RCC SLABS:

Providing & laying controlled reinforced cement concrete as per standard structural and architectural specification using 20MM downsized aggregates at any depth or heights including all formworks, centering, shuttering, scaffolding, compacting with vibrators, curing.

Concrete mix shall be of (1:2:4) grade.

Concrete pouring shall be machine mixed and mechanically vibrated.

NOTE: Water proof admixture will be added in first floor slab concrete mix

PARAPET WORK:

Single brick work (10 cm) combined with GP PIPE (front) for max height of 80 cm shall be used for the parapet work.

PCC BELOW FLOORING:

Plain Cement Concrete 1:4:8 using 40MM/20MM downgraded aggregates as per standard structural and architectural specification.

REINFORCED STEEL:

Fixing steel reinforcement (ISI TMT,500D) Kalliyath Brand or eqv. for RCC in all items, work including transporting, recoiling, cutting, straightening, bending and placing in position at all levels & binding with binding wire.

CEMENT:

Ordinary Portland cement or Portland pozzolana cement of Ambuja / JSW / **Ultratech (concrete only)** or equivalent shall be used for all the works.

SAND:

Good quality crushed M-sand shall be used for all RCC and super structural works, good quality crushed M-sand which is specially graded for the plastering purpose shall be used for all plastering works.

CEILING PLASTERING WORK:

Ceiling plastering work shall be in 1:3 cement mortar, below 10MM thick.

INSIDE PLASTERING WORK:

Inside plastering work shall be in cement mortar 1:5, 9 to 12 MM thick

OUTSIDE PLASTERING WORK:

Outside wall plastering work shall be in cement mortar 1:4, 12 to 15 MM thick.

TERRACE PLASTERING WORK:

Outside wall plastering work shall be in cement mortar 1:3, 12 to 15 MM thick.

NOTE: Water proofing admixture added in terrace plastering mix

SEPTIC TANK & RAINWATER STORAGE TANK:

Septic tank & Rain water storage tank shall be made as per the standard size & capacity. (For the full Effective rainwater harvesting system will cost extra) Readymade concrete tank

Two-Chamber Arrangement

A residential septic tank can be divided approximately:

Inlet → Chamber 1 → Partition/Baffle → Chamber 2 → Outlet → Soak Pit / Treatment System

The first chamber provides the main settling and digestion volume; the second chamber provides additional settling before discharge to the subsequent treatment/disposal system.

ELECTRICAL WORKS:

Cables	Finolex or Polycab/RR or Approved Equivalent
Switches & Sockets	Modular Switches & Sockets / Approved equivalent
Metal Boxes	Indoasian / Polycab or Equivalent
Distribution Board (DB)	Legrand/L&T

Final fittings such as fancy lightings, tube lights & ceiling fans should be provided by the client and actual labour charges extra.

DETAILS OF ELECTRICAL POINTS:

1. In all rooms 3 light points, one fan point and two socket point shall be provided
2. One socket point and one TV point(3skt) shall be provided in living room.
3. Three AC point and one geyser point shall be provided in all bedroom/Bath.
4. One power point, Motor point and three Nos of 6A socket points will provide in Kitchen.
5. One power point shall be provided in terrace for Washing Machine.
6. One socket point and one mirror lamp point shall be provided in Master bed room bath.
7. One mirror lamp point shall be provided in Dinning wash area.
8. DB and MCB's (L&T or Legrend) Three Phase

— DESIGN • BUILD • DELIVER —
— BUILDING DREAMS IN TO REALITY —

PLUMBING AND SANITARY WORK:

Complete plumbing and Sanitary works shall be executed by the contractor; using the below mentioned Brands

PVC Pipes	Supreme/Approved Equivalent
CPVC Pipes	Supreme/Approved Equivalent
CP fittings	Cera/Jaquar or Approved Equivalent
Sanitary (WC, WASH BASIN)	Cera/Jaquar or Equivalent
Water Tank	Aqua or Equivalent

PRICE DETAILS:

MASTER BEDROOM:

Closet	MRP 16,000/-
Health faucet	MRP 1200/-
Angle valve	MRP 600/-
Wash basin for toilet	MRP 3000/-
Wash basin tap	MRP 1400/-
Diverter with exposed part	MRP 7000/-
Shower head and arm	MRP 1200/-
Spout	MRP 1200/-

NORMAL ROOMS:

Closet	MRP 14,000/-
Health faucet	MRP 1000/-
Angle valve	MRP 450/-
Wash basin for toilet	MRP 2500/-

Wash basin tap	MRP 1000/-
Shower head and arm	MRP 1500/-
Long body tap	MRP 1000/-
Wash basin for dining	MRP 3500/-
Wash basin tap	MRP 1200/-

DETAILS OF PLUMBING POINTS:

Bath room	EWC – 1 Nos, Health faucet – 1Nos, Shower set – 1 Nos, Wash Basin – 1Nos.
Tap	1 Nos, Spout – 1 Nos shall be provided.
Kitchen	Kitchen Sink – 1Nos, Sink Tap – 1Nos shall be provided.
External	Water Taps – 2Nos shall be provided.
Terrace	Water Tap – 1Nos for Washing Machine shall be provided.
Dining Room	One wash basin and basin Tap shall be provided.

NOTE: Mixer tap/Diverter considered in 1 no toilets

HANDRAILS:

GI/SS handrails in stair case areas (considered total 10 meters)

Maximum price 2250/m

Balcony area Hand rails not considered, client should pay the actual cost after Finalization of 3D elevation if any.

— DESIGN • BUILD • DELIVER —
— BUILDING DREAMS IN TO REALITY —

FLOORING TILES:

160cm x 80cm vitrified floor tiles shall be used for all carpet areas; except bathrooms. (Choice of design, color & brand as per the client; priced at maximum rate of MRP Rs.75/- per Sq.ft incl.gst) epoxy joint fillings included in all floor areas.

SKIRTING TILE WORK:

Hi-gloss Nano technology vitrified floor tiles shall be used for all Skirting portions (10Cm Height).

KITCHEN DADOING WALL TILES:

Dadoing tile work s shall be done above the kitchen slab with good quality tiles (Size: 45 x 30 CMS) (Choice of design, color & brand as per the client; priced at maximum rate of MRP Rs.55/- per Sq.ft)incl. Gst

KITCHEN TOP:

Good quality granite slabs shall be used for the kitchen top. (Priced at Max.Rate of MRP Rs.220/- per Sq.ft) incl. Gst.

BATHROOM FLOORING TILES:

Good quality anti-skid tiles shall be used for all bathrooms. Size: 60 x 60 Cms. (Choice of design, colour & brand as per the client; priced at maximum rate of MRP Rs.60/- per Sq.ft) epoxy joint fillings must costs extra.incl. gst

BATHROOM WALL TILES:

Good quality bathroom Wall Tiles (Size: 60 x 60 CMS) of High lighter Model up to a maximum height of 7 Feet shall be used (Choice of design, colour& brand as per the client; priced at maximum rate of MRP Rs 60/- per Sq.ft). Epoxy joint fillings must cost extra. incl. Gst

BATHROOM DOORS:

All bathroom doors shall be done using branded pvc doors. (Choice of design, colour & brands per the client; priced at maximum rate of Rs.3000/- per door) incl. Gst

PUTTY WORKS:

Putty works shall be done in all the interiors areas
(Brand: Asian, Birla or JK Wall Putty)

Two coats of putty, one coat of cement primer and Two coat of Asian/Dulux/Berger paints shall be used for all internal walls and in external one coat of primer and two coat of Emulsion (Dulux/Asian/Berger). (Max Price-300-350/L)

JOINERY DETAILS:

Sl. No.	Joinery Item	Frame	Shutter / Door	Glass / Hardware	Remarks
1	Main Entrance Door	Teak wood frame	Teak wood shutter – single shutter	Clear/approved finish; Lock ₹2,500/No.	Premium main entrance door
2	Windows	Anjily wood frame	Mahogany wood shutter	Clear glass	Complete with hardware and finishing
3	Back Door	Anjily wood frame	Mahogany wood shutter	As required	Complete with hardware
4	Balcony Door	Anjily wood frame	Mahogany wood shutter	Clear glass where applicable; Latch as required	Complete with hardware
5	Internal Room Doors	Anjily wood frame	Flush door shutter	Door lock ₹1,000/No.	All bedrooms and other internal rooms
6	Toilet Doors	Anjily frame / as per design	Flush door shutter	Door lock ₹1,000/No.	Moisture-resistant finish recommended
7	Window Grills	—	GI pipe grill	—	Grills to be provided for maximum/all required windows

CONCLUSION OF WORK:

1. Civil Work
2. Electrical Work
3. Plumbing Work
4. Flooring work
5. Windows and Doors work (Joinery)
6. Painting Work

Our rate for full work is Rs 2100/sq.ft-



PAYMENT SCHEDULE

1	MOBILIZATION ADVANCE	20% OF TOTAL CONTRACT
2	WORK UP TO GROUND FLOOR LINTEL	12.5% OF TOTAL CONTRACT
3	WORK UP TO FIRST FLOOR LINTEL	12.5% OF TOTAL CONTRACT
4	FINAL SLAB COMPLETION	12.5% OF TOTAL CONTRACT
5	PLASTERING WORK COMPLETION	10% OF TOTAL CONTRACT
6	FLOORING WORK COMPLETION (50% Material @ site,50% After stage completion)	10% OF TOTAL CONTRACT
7	PAINTING WORK COMPLETION (50% Material @ site,50% After stage completion)	10% OF TOTAL CONTRACT
8	FINAL FIXTURES COMPLETION (50% Material @ site,50% After stage completion)	10% OF TOTAL CONTRACT
9	FINAL PAYMENT AFTER KEY HAND OVERING	2.5% OF TOTAL CONTRACT



INCLUSIONS, EXCLUSIONS AND PAYMENT SCHEDULE

A INCLUSIONS		
1	Septic tank	1750 L (Concrete)
2	Rain water harvest tank	Normal for approval
3	Water tank	1000 L White
4	Inverter point	Full control mode
5	AC point in 3 Bed room	AC pipe and sand box provision in all other rooms
6	Windows, Doors and Grill painting	
7	Water heater point in 3 bedrooms	
B EXCLUSIONS		
1	Light fittings	Not in contract
2	Compound wall	Not in contract
3	Paving tiles	Not in contract
4	Landscaping	Not in contract
5	Paper works from Govt. Authorities	Not in contract
6	Solar system	Not in contract
7	ID work	Not in contract
8	Bore well / Ring well, Motor	Not in contract
9	External stone / Marble / Tile cladings	Not in contract
10	Gate	Not in contract
11	Toilet glass partitions	Not in contract
12	Roof tiles	Not in contract
13	GI stairs to the roof	Not in contract

All additional works beyond the defined contract scope will be carried out separately from the contract amount. **A detailed** budget and quotation **for such works will be** submitted for your review and approval prior to commencement

Terms and conditions

1. The actual Area of building shall be taken from site after completion of works.
2. All material Shall be supplied by the contractor, Space for stacking materials should be provided near the plot. If lead is more than 25 m, extra payment shall be provided by the employer.
3. Water and Electricity should be provided by client at free of cost.
4. If there are any deviation or changes in the signed approved drawing (suggestion from client), the client should pay extra payment for extra work
5. For all additional works, actual cost with 15% CP or the rate agreed by both client and contractor, will be paid by the client.
6. Delaying of part payment will affect the overall progress of work.
7. Delaying of Material selection will affect the work progress
8. This rate will be in effect only for the duration of this contract (8 months).

